

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-212.37-0000

LEASE NAME Morton

WELL NUMBER A-4

 Ft. from S Section Line

 Ft. from E Section Line

SW NW SW

SEC. 35 TWP. 34 RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 3-24-88

Plugging Completed 3-30-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Edmiston Oil Company, Inc.

1260 Ks. St. Bank Bldg.

ADDRESS Wichita, Kansas 67202

PHONE# (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4825'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	327'	none
				4-1/2"	4824'	3556'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4700' and 4 sacks cement. Shot pipe @3827', 3630', 3556', pulled a total of 87 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 150 cement, 60/40 pos, 6%gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. RECEIVED 0050

Address Box 347 Chase, Kansas 67524 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss. APR - 4 1988

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and I have sworn that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso


Box 347

(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 31st. day of March, 1988

Irene Hoover
 Notary Public

My Commission Expires:



CONTRACTOR'S WELL LOG

OCT 22 1981

OPERATOR:	Ram Petroleum Company
CONTRACTOR:	Union Drilling CO., Inc.
LEASE NAME:	Morton #4
LOCATION:	SW NW SW Section 35-34S-12W Barber County, Kansas
COMMENCED:	08-25-81
COMPLETED:	09-03-81

0	305	Redbed
305	4056	Shale
4056	4283	Shale & Lime
4283	4478	Lime & Shale
4478	4612	Shale & Lime
4612	4722	Lime & Shale
4722	4820	Lime
4820		TD

We certify that the above foregoing is a true and correct copy of the log on the Morton #4, SW NW SW Section 35-34S-12W, Barber County, Kansas.

Union Drilling CO., Inc.

R.D. Messinger
 R.D. Messinger

STATE OF KANSAS)
)SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 14th day of September, 1981.

My appointment expires:

12-24-84

Shirley A. Gallegos
 Shirley A. Gallegos
 Notary Public

