

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

*Amended Report
WELL PLUGGING RECORD
K.A.R.-82-3-117

15-007-00215-00-01

Corrected CP-4

API NUMBER N/A
LEASE NAME Vestal L. Cook Unit
WELL NUMBER I-SWD

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div. *
office within 30 days.

990*2310 Ft. from S Section Line
990 Ft. from E Section Line

LEASE OPERATOR Mobil Oil Corporation

SEC. 17 TWP. 34S RGE. 12 0200 (W)

ADDRESS P.O. Box 5444, Denver, CO 80217

COUNTY Barber

PHONE# (303) 298-2696 OPERATORS LICENSE NO. 5208

Date Well Completed 3/19/56

Character of Well SWD

Plugging Commenced 9/12/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/18/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom _____ T.D. 4795

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				9 5/8"	357	
				5 1/2"	4794	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Rigged up Hayes Well Service, spotted sand back to 4648', spotted 5 sx common cement on top of sand. Rigged up Dia-Log, ran free point, cut csg. off @ 2593'. Recovered 79 jts. 5 1/2" csg.

Rigged up B-J Titan, pumped down surface csg. w/2 sx hulls, 15 sx gel, 50 sx cement, 9 5/8" csg. plug, 10 sx gel, 150 sx 60/40 pos w/2% gel, max. psi 450#, min. 250#, 200# on I.S.I.P.

(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Hayes Well Service License No. _____

Address Attica, KS

STATE OF Colorado COUNTY OF Denver

STATE CORPORATION COMMISSION
SS. 1-1-87

J. E. Dawson (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have known the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. E. Dawson J. E. Dawson

(Address) Producing Accounting Supervisor

P.O. Box 5444, Denver, CO 80217

SUBSCRIBED AND SWORN TO before me this 15th day of October, 19 86

Deborah A Cavette
Notary Public

My Commission Expires: MY COMMISSION EXPIRES 7/2/90

* R.E. Edscom 12-23-86
Subscribed & sworn to before me this 23rd day of
December, 1986.

Deborah A Cavette
Notary
Form CP-4
Revised 08-84

MY COMMISSION EXPIRES 7/2/90

Ran wire line, tagged cement at 84' from surface. Dumped 1½ yds. ready-mix concrete to fill 9 5/8" to surface. Welded plate on csg. Rigged down equipment, moved off. Plug and abandonment witnessed by Jack Luthi, K.C.C. representative.

FOR GAI

