


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

BARBER County. Sec. 24 Twp. 34 Rge. 14 (E) (W) est.  
Location as "NE/CNW/SW" or footage from lines Center S/2 S/2 NE/4  
Lease Owner E. H. Adair, et al.  
Lease Name GRAVES B Well No. 1.  
Office Address 1019 E. Second Street, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry-hole.  
Date well completed 2-2 19 57  
Application for plugging filed 2-2 19 57  
Application for plugging approved 2-2 19 57  
Plugging commenced 2-2 19 57  
Plugging completed 2-2 19 57  
Reason for abandonment of well or producing formation \_\_\_\_\_

A dry-hole.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well M. A. RIVES, Box 8, PRATT, KANSAS.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5390 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
(Copy of driller's log attached hereto.)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged at 4700 feet, cemented 50 sacks bulk. Bottom plug at 300 feet with 25 sacks. Top plug at 35 feet with 10 sacks.

STATE CORPORATION COMMISSION  
FEB 15 1957  
CONS. DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor E. H. Adair Oil Company  
Address 1019 East Second Street, Wichita 7, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
K. W. Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. W. Johnson  
1019 E. Second Street, Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of February, 19 57

My commission expires Sept. 15, 1957. L. Hill. Notary Public.

PLUGGING  
FILE SEC. 24 T. 34 R. 14W  
BOOK PAGE 138 LINE 30

15-007-00399-0000

E. H. Adair Oil Company  
1019 East Second St.  
Wichita 7, Kansas.

E. H. Adair Oil Company, et al,  
Graves No. 1 - B  
Center of S/2 of S/2 of NE/4 of  
Sec. 24-34-14 West,  
Barber County, Kansas.


Elevation: 1638 K.B.

Comm: 1-7-57  
Comp.: 2-2-57  
Contractor:  
E.H. Adair - Rig No. 1  
8-5/8 @ 347 ft. w/225 sax.

Pro. D. & A.

Figures indicate bottoms of Formations

Red shale	to	924	Lime	to	4551
Shale & shells		1830	Black shale		4554
Lime & shale		2091	Lime		4577
Lime		2203	Black shale		4382
Shale		2260	Lime		4610
Shale & lime		2382	Dark shale		4612
Shale		2400	Lime, slightly		
Lime & shale		3152	shaley		4704
Shale		3323	Dolomite, show		
Shale & lime		3450	of gas		4759
Shale		3560	Dolomite, dense		4846
Shale & lime		3690	Lime		4865
Lime		3696	Dolomite		4919
Shaley lime		3727	Dolomitic		
Shale		3751	limestone		4953
Sand		3877	Shaley lime		4999
Shale		3913	Lime		5030
Lime & shale		3949	Shale, limey		5044
Black shale		3953	Lime, shaley		5068
Limey shale		3969	Shale, black		5125
Lime		4034	Lime & cherty		
Shale		4125	lime		5268c
			Shale		5294
			Sand		5300
			Shale &		
			sandy shale		5390

  
K. W. Johnson - Geologist.

2-15-57  
DIVISION  
KANSAS

PLUGGING  
FILE SEC 24 T. 34 R. 14 W  
BOOK PAGE 138 LINE 30