

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Barber SEC. 12 TWP. 34S RGE. 14 ~~EW~~  
 Location as in quarters or footage from lines:  
C SW/4 SE/4 SE/4


Lease Owner Albert Bouziden  
 Lease Name Birdie Well No. 12-15  
 Office Address 5600 N. May Ave., Suite 145, OKC, OK 73112  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed 11-2-82  
 Application for plugging filed 11-23-82  
 Plugging commenced 11-2-82  
 Plugging completed 11-2-82  
 Reason for abandonment of well or producing formation Dry hole

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes


Name of Conservation Agent who supervised plugging of this well Paul Luthi  
 Producing formation None Depth to top N/A bottom N/A T.D. 4985'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0	1093'	8 5/8"	10/20/82	

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

1st cement plug at 961' to 1140' w/60 sacks  
2nd cement plug at 500' to 580' w/20 sacks  
Top plug from surface to 40' w/10 sacks  
Rathole circulated w/10 sacks  
All cement displaced to balance w/fresh water  
Cement type 50/50 poz, 2% gel, 3% CaCl  
Hole full of approx. 9.2 lb/gal drilling mud



(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Sun Oil Well Cementing Medicine Lodge, KS

STATE OF Oklahoma COUNTY OF Oklahoma, ss.  
Mark Liddell (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Mark Liddell  
5600 N. May Ste 145, OKC, OK 73112  
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December, 19 82

Susan D. Wright  
 Notary Public.

My Commission expires: May 12, 1984