

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber

County, Sec. 12 Twp. 34S Rge. (E) 14 (W)

Location as "NE/CNW&SW¼" or footage from lines C NE/4 NW/4 SE/4

Lease Owner Skelly Oil Company

Lease Name Birdie Clarke Well No. 2

Office Address Box 1650, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 16, 1964

Application for plugging filed June 17, 1964

Application for plugging approved June 18, 1964

Plugging commenced June 16, 1964

Plugging completed June 17, 1964

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (verbally)

Mr. A. Elving

Name of Conservation Agent who supervised plugging of this well  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4925 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE OD	PUT IN	PULLED OUT
Mississippian	Dry	4842'	4925'	8-5/8"	474'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

50 sacks cement	4925' to 4775'
Mud laden fluid	4775' to 475'
Rock bridge	475' to 465'
25 sacks of cement	465' to 390'
Mud laden fluid	390' to 40'
Rock bridge	40' to 30'
15 sacks of cement	30' to 5'
Surface soil	5' to Surface

RECEIVED  
STATE CORPORATION COMMISSION

JUL 31 1964

7-31-64  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address Wichita, Kansas

STATE OF Nebraska, COUNTY OF Red Willow, ss.  
C. F. Bass (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. F. Bass  
P.O. Box 649, McCook, Nebraska 69001  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 19 64

My commission expires June 13, 1969  
C. E. Lindsey Notary Public.

JUN 23 1964

6-23-64

CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S LOG

COMPANY: Skelly Oil Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: BIRDIE CLARK #2  
 LOCATION: NE NW SE Sec. 12-34-14  
 BARBER COUNTY, KANSAS  
 COMMENCED: 6-3-64  
 COMPLETED: 6-17-64

---

0	417	Red Rock & Shale
417	1945	Shale & Shells
1945	1965	Lime
1965	2610	Lime & Shale
2610	3280	Shale & Lime
3280	3680	Lime & Shale
3680	3853	Shale & Lime
3853	4545	Lime & Shale
4545	4926	Lime
	<u>4926</u>	<u>Rotary Total Depth - D. &amp; A.</u>

---

Set 8 5/8" used surface casing @ 485' with 275 sacks HA5 Posmix

---

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Birdie Clark #2 well, located NE NW SE of Section 12, Township 34, Range 14, Barber County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 22nd day of June, 1964.

Ulanda Nichols  
 Ulanda Nichols

My Commission Expires  
 April 1, 1967