


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Take Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

BARBER County. Sec. 8 Twp. 34 Rge. 14 (E) (W) ✓  
Location as "NE/CNW/SW" or footage from lines C 5/2 - NE  
Lease Owner H. C. BENNETT  
Lease Name W. H. TITTLESEY Well No. 1  
Office Address 1212 UNION NAT'L Bldg. WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 11-26-61 19\_\_  
Application for plugging filed 8-19-65 19\_\_  
Application for plugging approved 8-19-65 19\_\_  
Plugging commenced 9-3 1965  
Plugging completed 9-7 1965  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4797 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Missouri</u>		<u>0</u>	<u>427</u>	<u>1 3/8</u>	<u>227</u>	<u>0</u>
		<u>0</u>	<u>4796</u>	<u>4 1/2</u>	<u>4796</u>	<u>4255</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Globe Cementing Co pumped 100 bags cement to 4327  
Pull 4720 ft 4 1/2" pipe - mud hole to 200 ft - 20 ft  
rock bridge - dump 5 yds ready mix cement - mud to 35 ft  
10 ft rock bridge - dump 1 yds cement

RECEIVED  
STATE CORPORATION COMMISSION

SEP 29 1965  
9-29-65

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor RALPH CONSTOCK PIPE PLUGGING Permit # 490  
Address STATE ROAD KS

STATE OF Kansas COUNTY OF Sedgewick ss.  
Jack Sloan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Sloan

SUBSCRIBED AND SWORN TO before me this 7th day of September 19 65

My commission expires June 3, 1967  
James C. Smith Notary Public.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SUNRAY MID-CONTINENT OIL CO.  
Farm- Whittlesey Est. No. 1

SEC. 8 T. 34 R. 14W  
C S/2 NE

Total Depth. 4797'  
Comm. 11-8-61 Comp. 11-26-61  
Shot or Treated.  
Contractor. Garvey Drig.  
Issued. 4-28-62

County Barber  
KANSAS



Elevation. 1642' DP

Production. 610,000 CPG

CASING:

13 3/8" 227' cem w/250 sx.  
4 1/2" 4796' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface clay & red bed	190
red bed	900
shale & shells	960
shale	1050
shale & gyp	1600
shale, lime & chert	1700
shale & lime	1965
lime & shale	2195
shale & lime	2303
lime & shale	2353
shale & lime	3188
lime & shale	3262
shale & lime	4000
sandy shale	4020
lime & shale	4060
shale & lime	4185
lime & shale	4210
lime	4340
lime, shale & chalk	4381
lime	4582
lime & shale	4765
lime & chert	4797
Total Depth	

TOPS: SCOUT	
Heebner	3926
Lansing	4132
Base Kansas City	4543
Mississippi	4709

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 29 1965  
9-29-65  
CONSERVATION DIVISION  
Wichita, Kansas