


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Barber County, Sec. 4 Twp. 34 Rge. 14 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines C SE SW  
Lease Owner Specter Pipe & Supply Co., Inc.  
Lease Name Davis Ranch Well No. G-1  
Office Address Box 169 Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) gas  
Date well completed 8-8-60 19  
Application for plugging filed June 16, 1973 19  
Application for plugging approved June 19, 1973 19  
Plugging commenced 7-30-73 19  
Plugging completed 8-2-73 19  
Reason for abandonment of well or producing formation Depleted  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Mississippi Depth to top 4607 Bottom 4729.75 Total Depth of Well 4730' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	4730'	3388.41'
				13 3/8"	190'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 4600'. Mixed and dumped 3 sacks cement thru dump bailer.  
Mudded hole to 120' - set 20' rock bridge. Filled hole with 5 yards ready-mix to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 20 1973  
8-20-73  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Russell, ss.  
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morgan Specter  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 1973

Richard M. Lindahl  
Notary Public.

My commission expires May 21, 1975

15-007-01095-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company- CHAMPLIN OIL & REFINING CO.  
Farm- Davis Ranch "G" No. 1

SEC. 4 T. 34 R. 14W  
Approx. C SE SW

Total Depth. 4730'  
Comm. 7-22-60 Comp. 8-8-60  
Shot or Treated.  
Contractor. Armer, Inc.  
Issued. 11-19-60

County Barber  
KANSAS



Elevation. 1571' DF

Production. 77 BOPD &  
995,000 CFG

Figures indicate Bottom of Formations.

sand, shale & shells	130
red bed & lime shells	200
red bed & shale	340
red shale & shells	960
shale & shells	1360
shale, shells & lime	1590
shale & shells	1735
lime	2175
lime & shale	2840
shale	2900
lime & shale	4140
lime	4487
lime & shale	4615
lime	4642
cherty lime	4662
Mississippi lime	4730
Total Depth	

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1973  
6-26-73  
CONSERVATION DIVISION  
Wichita, Kansas

TOPS:	SAMPLE	ELECTRIC
Heebner	3823	3834
Toronto	3840	3848
Douglas	3858	3874
Lansing-Kansas City	4033	4030
Base Kansas City		4510
Marmaton		4522
Cherokee		4594
Mississippi	4607	4603