


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 2 Twp. 34S Rge. 14W (E) (W)  
Location as "NE/CNW&SW%" or footage from lines. NW NE SW  
Lease Owner. Skelly Oil Co.  
Lease Name Sooter Well No. A-#1  
Office Address Box 649, McCook, Nebr.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 8-19-65 19  
Application for plugging filed 8-19-65 19  
Application for plugging approved 8-19-65 19  
Plugging commenced 8-19-65 19  
Plugging completed 8-19-65 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	370'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @ 300' 1/2 sk. hulls 25 sks. cement through drill pipe  
Plug @ 40' 1/2 sk. hulls 10 sks. cement  
5 sks. cement in rathole

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1965

8-24-65

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lehen Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23 day of August 19 65

My commission expires October 19, 1968

Notary Public.

DRILLER'S LOG

COMPANY: Skelly Oil Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: SOOTER A-#1  
 LOCATION: NW NE SW Sec. 2-34S-14W  
 BARBER COUNTY, KANSAS  
 COMMENCED: 8-7-65  
 COMPLETED: 8-19-65

0	735	Redbed
735	1070	Redbed & Shale
1070	1896	Shale & Lime
1896	2065	Lime & Shale
2065	2240	Lime
2240	2660	Lime & Shale
2660	3730	Shale & Lime
3730	4015	Lime & Shale
4015	4110	Shale & Lime
4110	4808	Lime
	<u>4808</u>	<u>RTD - D. &amp; A.</u>

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 AUG 24 1965  
 8-24-65  
 CONSERVATION DIVISION  
 Wichita, Kansas

8 5/8" used surface casing 32# set @ 370' with 300sacks Common HA5

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Sooter A-#1 well located NW NE SW of Section 2, Township 34 South, Range 14 West of Barber County, Kansas, as reflected by the records of Leben Drilling, Inc.

*Leslie Kite*

Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 23rd day of August, 1965.

*E. M. Benoit*

E. M. Benoit

My Commission Expires:  
 October 19, 1968