

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County, Sec. 3 Twp. 34S Rge. 14W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
75' SW of C of S/2 NW/4 NW/4

Lease Owner Braden-Deem, Inc.  
Lease Name GORDON (Twin) Well No. 1

Office Address 200 E. First Street, Wichita, Ks 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole


Date Well completed Jan. 191980  
Application for plugging filed(verbally) Jan. 191980  
Application for plugging approved(verbally) Jan. 191980  
Plugging commenced Jan. 191980  
Plugging completed Jan. 191980

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation Depth to top Bottom Total Depth of Well 4780'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. 4780'  
Set 1st plug at 720' with 50 sacks  
2nd plug at 300' with 20 sacks  
3rd plug at 40' solid bridge with 10 sacks  
rathole with 5 sacks.  
Cemented with 50/50 posmix, 6% gel.  
Plug was down at 5:00 p.m., January 19, 1980.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of January, 1980.



Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

RECEIVED  
STATE CORPORATION COMMISSION

JAN 30 1980  
1-30-80  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

OPERATOR: Braden-Deem, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Gordon #1 (Twin)  
 LOCATION: 75' SW of C of S/2 NW/4 NW/4,  
 Section 3-34S-14W, Barber County,  
 Kansas  
 SPUD DATE: January 08, 1980  
 COMPLETION DATE: January 19, 1980

0	15	Top soil
15	627	Gyp and red bed
627	1173	Red bed and shale
1173	1684	Shale
1684	1892	Red bed and shale
1892	4715	Lime and shale
4715	4725	Dolomite and shale
4725	4780	Mississippian
	4780	Rotary Total Depth

Spud hole at 11:00 p.m., January 08, 1980. Drilled 1180' of 12 1/4" hole. Set at 1177' with 8-5/8"-24# casing. Cemented with 300 sacks of Halliburton lite, 3% Ca.Cl., followed with 200 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Float held. Plug was down at 11:30 p.m., January 09, 1980.

T.D. 4780'. Set 1st plug at 720' with 50 sacks, 2nd plug at 300' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks and 5 sacks in the rat-hole. Cemented with 50/50 posmix, 6% gel. Plug was down at 5:00 p.m., January 19, 1980.


STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Gordon #1 (Twin), 75' SW of C of S/2 NW/4 NW/4, Section 3-34S-14W, Barber County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid as of this 28th day of January, 1980.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 30 1980  
 1-30-80  
 CONSERVATION DIVISION  
 Wichita, Kansas