

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,266 -0000

LEASE NAME Alberding

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3

2970 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 34 TWP. 34S RGE. 12 ~~XXX~~ (E) or (W)

COUNTY Barber

Date Well Completed 1-27-82

Plugging Commenced 11-20-89

Plugging Completed 11-20-89

LEASE OPERATOR Gore Oil Company

ADDRESS 125 N. Market, #1750, Wichita, KS 67202

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4770' Bottom T.D. 4840'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	oil/gas	0	313	10 3/4	313	0
				4 1/2	4839	3700

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug back with sand to 4720'. Dump 4 sx cement. Plug with 300 lbs. hulls, 10 sx gel, 50 sx 60/40 - 6%, 10 sx gel, 100 lbs. hulls, 130 sx 60/40 - 6% to surface. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Titan License No. n/a

Address Box 368, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Sedgwick, ss.

I, Scott W Scheuerman, an (Employee of Operator) ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Scott W Scheuerman

(Address) 125 N. Market, #1750, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 89

11-30-89
Wichita, Kansas
My Commission Expires: 1-7-91

Rebecca K Crawford
Notary Public



CONTRACTOR'S WELL LOG

OPERATOR:	Ram Petroleum Corporation
CONTRACTOR:	Union Drilling Co., Inc.
LEASE NAME:	Alberding #3
LOCATION:	SW SE NE Section 34-34S-12W Barber County, Kansas
COMMENCED:	January 8, 1982
COMPLETED:	January 17, 1982

FEB 1 1982

0	318	Redbed	Set 10-3/4" @ 313' w/300 sxs
318	690	Redbed & shale	common cement 2% gel, 3% CC
690	4498	Shale	
4498	4626	Lime & shale	
4626	4840	Lime	
4840		RTD	

We certify that the above foregoing is a true and correct copy of the log on the Alberding #3, SW SE NE Section 34-34S-12W, Barber County, Kansas.

Union Drilling Co., Inc.

R. D. Messinger
(R. D. Messinger)

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 21st day of January, 1982.

My appointment expires:

12-24-84

Shirley A. Gallegos
Shirley A. Gallegos
Notary Public

OCT 24 1989

CONSERVATION DIVISION
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1989
10-26-89
CONSERVATION DIVISION
Wichita, Kansas

