

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-212,65-0000

LEASE NAME Alberding

WELL NUMBER #2

 Ft. from S Section Line

 Ft. from E Section Line
 SW NW NE

SEC. TWP. RGE. (E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 3-30-88

Plugging Completed 4-12-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Edmiston Oil Company, Inc.

ADDRESS 1260 Ks. St. Bank Bldg.
 Wichita, Kansas 67202

PHONE#(316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4835'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	314'	none
				4-1/2"	4834'	3235'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4710' and 4 sacks cement. Shot pipe @3407', 3287', 3235', pulled a total of 79 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 8-5/8" plug and 150 cement, 60/40 Pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

Box 347

(Address) Chase, Kansas 67524

RECEIVED
 STATE CORPORATION COMMISSION
 SUBSCRIBED AND SWORN TO before me this 13th day of April, 19 88

4-15-88

APR 15 1988

My Commission Expires:

James Hoover
 Notary Public

CONSERVATION DIVISION
 Wichita, Kansas



CONTRACTOR'S WELL LOG

FEB 1 1982

OPERATOR:	Ram Petroleum Corporation
CONTRACTOR:	Union DRilling Co., Inc.
LEASE NAME:	Alberding #2
LOCATION:	SW NW NE Section 34-34S-12W Barber County, Kansas
COMMENCED:	December 30, 1981
COMPLETED:	January 7, 1982

0	315	Redbed	Set 10-3/4" @ 314' w/300 sxs
315	1355	Redbed & shale	common 3% gel, 3% CC
1355	4127	Shale	
4127	4500	Lime & shale	
4500	4618	Shale	
4618	4835	Lime	
4835		RTD	

We certify that the above foregoing is a true and correct copy of the log on the Alberding #2, SW NW NE Section 34-34S-12W, Barber County, Kansas.

Union Drilling Co., Inc.

R. D. Messinger

 R. D. Messinger

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 13th day of January, 1982.

My appointment expires:

 12-24-84

Shirley A. Gallegos

 Shirley A. Gallegos
 Notary Pbulic

