

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21,010-0000

LEASE NAME Terwert

WELL NUMBER #2

_____ Ft. from S Section Line

_____ Ft. from E Section Line
 SW NW SW

SEC. 34 TWP. 34 RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed _____

Plugging Commenced 4-5-88

Plugging Completed 4-12-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Edmiston Oil Company, Inc.

ADDRESS 1260 Ks. St. Bank Bldg.
 Wichita, Kansas 67202

PHONE # (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4815'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	324'	none
				4-1/2"	4814'	3441'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 4575' and 4 sacks cement. Shot pipe @3621', 3441', pulled a total of 83 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 8-5/8" plug and 150 cement, 60/40 pos, 6% gel.
Plugging Complete.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 13th day of April, 1988
 STATE CORPORATION COMMISSION

[Signature]
 Notary Public

My Commission Expires:

APR 15 1988
4-15-88
 CONSERVATION DIVISION
 Wichita, Kansas




CONTRACTOR'S WELL LOG

OPERATOR:	Ram Petroleum Corporation
CONTRACTOR:	Union Drilling Co., Inc.
LEASE NAME:	#2 Terwort
LOCATION:	SW NW SW Section 34-34S-12W Barber County, Kansas
COMMENCED:	October 10, 1980
COMPLETED:	October 19, 1980

0	329	Redbed	Set 8-5/8" at 324'
329	510	Redbed & shale	With 275 sacks common 2% gel. 3% Ca. Cl.
510	4170	Shale	
4170	4512	Shale & lime	
4512	4730	Lime & shale	
4730	4815	Lime	
4815		TD	

We certify that the above foregoing is a true and correct copy of the log on the #2 Terwort, SW NW SW Section 34-34S-12W, Barber County, Kansas .

Union Drilling Co., Inc.



R. D. Messinger

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 23rd day of October, 1980.

My appointment expires:

6-2-82


Cynthia L. Romey-Notary Public