

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER. 15-007-210,32-0000

LEASE NAME Vogel

WELL NUMBER C-2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 34 TWP. 34 RGE. 12 (E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 3-10-88

Plugging Completed 3-15-88

LEASE OPERATOR Edmiston Oil Co., Inc.

1260 Ks. St. Bank Bldg.

ADDRESS Wichita, Kansas 67202

PHONE# (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Ks.

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	320'	none
				4-1/2"	4849'	3453'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4730' and 4 sacks cement. Shot pipe @3604', 3453', pulled a total of 84 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 150 cement, 60/40 pos, 6% gel.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of March 1988

RECEIVED
 STATE CORPORATION COMMISSION

James Hoover
 Notary Public

My Commission Expires:



MAR 28 1988
 3-28-88
 Form CP-4
 CONSERVATION DIVISION
 Wichita, Kansas
 Revised 07-86

CONTRACTORS WELL LOG

OPERATOR:	RAM PETROLEUM CORPORATION
CONTRACTOR:	UNION DRILLING CO., INC.
LEASE NAME:	VOGEL "C" #2
LOCATION:	SW NW SE SECTION 34-34S-12W BARBER COUNTY, KANSAS
COMMENCED:	DECEMBER 3, 1980
COMPLETED:	DECEMBER 12, 1980

0	778	REDBED & SHALE	SET 10-3/4" AT 320'
778	4145	SHALE	WITH 275 SACKS COMMON
4145	4367	LIME & SHALE	2% GEL., 3% CA. CL.
4367	4850	LIME	
4850		TD	

WE CERTIFY THAT THE ABOVE FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE VOGEL "C" #2, SW NW SE SECTION 34-34S-12W, BARBER COUNTY, KANSAS.


UNION DRILLING CO., INC.

E. A. Falkowski
E. A. FALKOWSKI

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC IN AND FOR THE AFORESAID COUNTY AND STATE AS OF THIS 16th DAY OF DECEMBER, 1980.

APPOINTMENT EXPIRES:



Cynthia L. Romey
CYNTHIA L. ROMEY-NOTARY PUBLIC