

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-212,35-0000

LEASE NAME Morton

WELL NUMBER A-2

 Ft. from S Section Line

 Ft. from E Section Line
 SW NE SE

SEC. 34 TWP. 34 RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 3-15-88

Plugging Completed 3-30-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Edmiston Oil Company, Inc.

ADDRESS 1260 Ks. St. Bank Bldg.
 Wichita, Kansas 67202

PHONE# (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4840'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"		none
				4-1/2"	4839'	3280'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4730' and 4 sacks cement. Shot pipe @3601', 3480', 3359', 3280', pulled a total of 80 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 150 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No.

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED
 STATE CORPORATION COMMISSION
 4-4-88
 APR - 4 1988

R. Darrell Kelso (Employee of Operator Edmiston Oil Company, Inc.) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 31st. day of March, 19 88

Irene Hoover
 Notary Public

My Commission Expires:



15-007-21235-0000

CONTRACTOR'S WELL LOG

SEP 6 1981

OPERATOR:
CONTRACTOR:
LEASE NAME:
LOCATION:


COMMENCED:
COMPLETED:

Ram Petroleum Corporation
Union Drilling Co., Inc.
#2 Morton
SW NE SE Section 34-34S-12W
Barber County, Kansas
August 5, 1981
August 14, 1981

0	318	Red bed	Set 8-5/8" @ 314' w300 sx
318	742	Red bed and shale	common cement, 2% gel, 3% CC
742	4523	Shale	
4523	4628	Shale and lime	
4628	4737	Lime and shale	
4737	4840	Lime	
4840		T. D.	

We certify that the above and foregoing is a true and correct copy of the log on the #2 Morton, SW NE SE Section 34-34S-12W, Barber County, Kansas

UNION DRILLING CO., INC.



R. D. Messinger, President

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 18th day of August, 1981.

My appointment expires:

6-2-82


Cynthia L. Romey-Notary Public