

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-007-21,031-00-01

LEASE NAME Vogel

WELL NUMBER C-1

         Ft. from S Section Line

         Ft. from E Section Line  
 SW SW SE

SEC. 34 TWP. 34 RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed         

Plugging Commenced 3-8-88

Plugging Completed 3-15-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Edmiston Oil Co., Inc.

1260 Ks. St. Bank Bldg.

ADDRESS Wichita, Kansas 67202

PHONE# (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4870'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Puf In	Pulled out
				10-3/4"	331'	none
				4-1/2"	4864'	3431'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Plugged off bottom with sand to 4450' and 4 sacks cement. Shot pipe @3811', 3612', 3431', pulled a total of 83 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 150 cement, 60/40 pos, 6% gel.  
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 18th day of March 1988

Notary Public - 1988

My Commission Expires:         



RECEIVED  
 STATE CORPORATION COMMISSION  
 3-21-88  
 CONSERVATION DIVISION  
 Wichita, Kansas Form CP-4 Revised 07-86

15-007-21031-00-01

CONTRACTORS WELL LOG

DEC 8 1980

OPERATOR:  
CONTRACTOR:  
LEASE NAME:  
LOCATION:

RAM PETROLEUM CORPORATION  
UNION DRILLING CO., INC.  
VOGEL "C" #1  
SW SW SE SECTION 34-34S-12W  
BARBER COUNTY, KANSAS  
NOVEMBER 23, 1980  
DECEMBER 1, 1980

COMMENCED:  
COMPLETED:

0	691	REDBED & SHALE
691	4259	SHALE
4259	4449	SHALE & LIME
4449	4607	LIME & SHALE
4607	4865	LIME
4865		TD

SET 10-3/4" AT 331'  
WITH 275 SACKS COMMON 2% GEL.,  
3% CA. CL.

WE CERTIFY THAT THE ABOVE FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE VOGEL "C" #1, SW SW SE SECTION 34-34S-12W, BARBER COUNTY, KANSAS.

UNION DRILLING CO., INC.

*[Handwritten Signature]*  
R. D. MESSINGER

STATE OF KANSAS     )  
                              )SS  
COUNTY OF SEDGWICK )

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC, IN AND FOR THE AFORESAID COUNTY AND STATE AS OF THIS 5th DAY OF DECEMBER, 1980.

MY APPOINTMENT EXPIRES:

6-2-82

*[Handwritten Signature]*  
CYNTHIA L. ROMNEY NOTARY PUBLIC