


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 34 Twp. 34 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C-SW-NE
Lease Owner Oleum, Inc.
Lease Name Good Well No. 1
Office Address Box 268, Darrouzette, Texas 79024
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Oil
Date Well completed 10-15- 1969
Application for plugging filed 5-16- 1977
Application for plugging approved 5-19- 1977
Plugging commenced 5-19- 1977
Plugging completed 5-23- 1977
Reason for abandonment of well or producing formation

Not Productive
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Buddy Metz
Producing formation Miss. Depth to top Bottom Total Depth of Well 4805
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	410	None
				4 1/2	4603	4000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped sand from 4805 to 4745'
4 sacks cement from 4745 to 4700'

Wooden Bridge at 320'
Rock from 320 to 310'

5 yards of ready mix to surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.
Elmo R. Morgenstern (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmo R. Morgenstern
Medicine Lodge, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1977.

Jessie Hamilton
Notary Public.

My commission expires April 4, 1978

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1977
5-31-77
CONSERVATION DIVISION
Wichita, Kansas

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
MAY 20 1977
5-28-77
OCCUPATIONAL DIVISION
Wichita, Kansas

GOOD #1-34
60' N of C SW NE Section 34-34S-12W
Barber County, Kansas

Commenced: September 27, 1969
Completed: October 15, 1969

OPERATOR - Nichols Drilling Company

DEPTH		FORMATION	REMARKS
From	To		
0	230	Red bed and shells	
230	410	Shale and red bed	Ran 14 joints of 8-5/8" casing, set @ 410' w/300 sacks cement.
410	1750	Shale and shells	
1750	2580	Lime and shale	
2580	2680	Shale	
2680	3625	Shale and lime	
3525	3730	Lime and sand	
3730	4425	Lime and shale	
4425	4767	Lime	
4767	4784	Lime and chert	
4784	4805	Lime	
4805	TD		Ran 154 joints of 4-1/2" casing, set @ 4803 feet w/150 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled 60' N of C SW NE Section 34-34S-12W, Barber County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 24 day of October, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

