

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21,189-00-0

LEASE NAME Morton A

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 34 TWP. 34 S RGE. 12 ~~XXX~~ (W)

COUNTY Barber

Date Well Completed 6-23-81

Plugging Commenced 11-21-89

Plugging Completed 11-21-89

LEASE OPERATOR Gore Oil Company

ADDRESS 125 N. Market, #1750, Wichita, KS 67202

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil/SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4802' Bottom T.D. 4865'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	oil/gas	0	330	10 3/4	330	0
			4864	4 1/2	4864	3200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug back with sand to 4400'. Dump 4 sx cement. Plug with 400 lbs. hulls, 10 sx gel, 50 sx 60/40 - 6%, 10 sx gel, 100 lbs. hulls, 130 sx 60/40 - 6% to surface. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Titan License No. n/a

Address box 368, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Sedgwick, ss.

I, Scott W Scheuerman, an (Employee of Operator) ~~XXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, #1750, Wichita, KS 67202

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 11-30-89
 NOV 30 1989

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 89

Cons. Div. Notary
 Wichita, Kansas

[Signature]
 Notary Public

My Commission Expires: 1-7-91

STATE OF KANSAS
 REBECCA K. CRAWFORD
 State of Kansas
 My Appt. Exp. 1-7-91

KANSAS DRILLERS LOG

COMPANY Ram Petroleum
 FARM Morton NO. 1

SEC. 34 T. 34S R. 12W
 LOC. SW SE SE

JUN 15 1981

ROTARY TOTAL DEPTH 4865'
 COMM. 5-26-81 COMP. 6-6-81
 CONTRACTOR Freeman Drilling Company
 ISSUED 6-12-81

COUNTY Barber

CASING

10 3/4" - set at 330' - w/300 sxs cement
 8 5/8"
 5 1/2"
 4 1/2" - set at 4864' - w/250 sxs cement

ELEVATION 1423'gr

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	939'
Red Bed and Sand	1699'
Lime and Shale	1985'
Shale and Sand	2240'
Lime and Shale	4865'
RTD	4865'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Gary Younger
 Gary Younger

State of Kansas)
) SS
 County of Sedgwick)

Subscribed and Sworn to before me, a Notary Public, in and for said county and state this 12th day of June, 1981.

Helen Pracht
 Helen Pracht - Notary Public

My Commission Expires:

June 4, 1985

