

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Harper

County. Sec. 13 Twp. 32S Rge. 6W (E) (W)

Location as "NE/CNW&SW¼" or footage from lines. NE NE NE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Pelzl Well No. 1

Office Address 780 Fourth National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 1 19 59

Application for plugging filed April 1 19 59

Application for plugging approved April 1 19 59

Plugging commenced April 1 19 59

Plugging completed April 1 19 59

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred W. Hampel

Producing formation Depth to top Bottom Total Depth of Well 4731 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	255'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set No. 1 Plug at 550' with 20 sacks cement; Set No. 2 Plug at 220' with 20 sacks cement; Set No. 3 Plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.
(Signature) By: *Raymond L. Bacon* V-P
780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June 19 59

My commission expires July 7, 1962

Mona L. Latier
Mona L. Latier Notary Public.

PLUGGING
FILE SEC. 13 T. 32R 6W
BOOK PAGE 43 LINE 30

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Pelzl No. 1
NE NE NE Sec. 13-32S-6W
Harper County, Kansas

Total Depth: 4731'

Elevation: 1341' RB
Production: D & A

Commenced: 3-10-59 Completed: 4-1-59

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 255' with 200 sacks cement.

Figures indicate bottom of formations:

Surface Sand & Shale	40'
Sand, Shale & Rock	256'
Shale & Shells	1090'
Lime & Shale	1470'
Lime (Ft. Riley)	1570'
Lime & Shale	3434'
Sand - Lime & Shale	3504'
Lime & Shale	3671'
Lime	3932'
Lime & Shale	4275'
Lime-Shale & Chert	4307'
"Cherty" Lime	4397'
Lime & Shale	4412'
Chert-Lime & Shale	4433'
"Cherty" Lime	4465'
Lime	4552'
"Cherty" Lime	4608'
Lime & Shale	4717'
Sand	4721'
Simpson Sand	4731'
Total Depth	4731'

TOPS

Heebner 30	3035'	(-1694)
Stalnaker	3418'	(-2077)
Lansing	3641'	(2300)
Cherokee shale	4084'	(-2743)
Mississippi	4285'	(-2944)
Simpson	4715'	(-3374)
Rotary Total Depth	4731'	(-3390)

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1959

CONSERVATION DIVISION
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: A. Bacon
Vice-President

Subscribed and sworn to before me this 20th day of April, 1959.

My Commission Expires:
July 7, 1962

PLUGGING	
FILE	SEC. 13 T. 32 R. 6 W
BOOK	PAGE 43 LINE 30

Mona L. Latier
Mona L. Latier - Notary Public