

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-21,190-00-00

LEASE NAME Drouhard

WELL NUMBER 32-13

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 13 TWP. 32 RGE. 6 XX or (W)

COUNTY Harper

Date Well Completed 4-28-89

Plugging Commenced 4-28-89

Plugging Completed 4-28-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Macey & Mershon Oil Inc.

ADDRESS 1600 Broadway Ste 2150 Denver, CO 80202 4970

PHONE# (303) 861-9183 OPERATORS LICENSE NO. 3964

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-27-89 (date)

by John Sanders (KCC District Agent's Name).

is ACO-1 filed? operator to be filed by operator If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4825'

Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @1000' w/35 sacks cement thru drill pipe

Next Plug: @ 600' w/35 " " " " " "

Next Plug: @260' w/35 " " " " " " 10 sacks in Rat Hole

Top Plug: @ 60' w/25 " " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Macey & Mershon Oil Inc.


STATE OF Kansas COUNTY OF Barton, ss. *Rec'd 5/1/89*

John Armbruster

(Employee of Operator) or XXXXXXXXXXXX of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Armbruster

(Address) P.O. Box 823 Great Bend, KS 67530



AND SWORN TO before me this 6th day of May, 19 89

Dorothy M. Hague
Notary Public

My Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: April 20, 1989
DATE COMPLETED: April 28, 1989

Pacey & Mershon OIT Inc.
DROUHARD #32-13
NE SW NE
Sec. 13, T32S, R6W
Harper County, Ks.

0 - 213' Topsoil, Sand, Red Bed, Shale
213 - 1245' Shale, Lime Streaks
1245 - 2636' Lime, Shale
2636 - 2870' Lime
2870 - 3306' Shale, Lime Streaks
3306 - 3765' Shale, Lime
3765 - 4293' Lime, Shale
4293 - 4620' Lime, Chert, Shale
4620 - 4805' Shale, Sand, Lime
4805 - 4825' Shale, Lime
4825' RTD

ELEVATION: 1330 K.B.

Surface Pipe: Set used
8-5/8", 24# pipe @212'
w/170 sacks 60/40 pozmix
2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

John Armbruster of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

John Armbruster

Subscribed and sworn to before me this 6th day of May 1989.



Dorothy M. Hague
Notary Public