

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15-077-20383-00-01

LEASE NAME Hostetler

WELL NUMBER B-1

 Ft. from S Section Line

 Ft. from E Section Line

SW NW NW
SEC. 10 TWP. 32 SRGE. 6W (E) or (W)

COUNTY Harper

Date Well Completed

Plugging Commenced 4-21-87

Plugging Completed 4-28-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947
Pratt, Kansas 67124

PHONE # (316) 672-7514 OPERATORS LICENSE NO. 5087

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #2 Wichita, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4612'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	266'	none
				4-1/2"	4506'	3816'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4250' and 4 sacks cement. Shot pipe @ 3816', pulled a total of 104 joints of 4-1/2" casing. Plugged surface with 4 hulls, 15 gel; 8-5/8" plug and 100 sacks cement, 60/40 pos, 6% gel. Max. Press. 500#, shut in 200#. Plugging Complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1987

Irene Hoover
Notary Public

My Commission Expires:

