

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

KCC.TMB  
 21380-0000

API NUMBER 15-007-213,79

LEASE NAME Graves B-2

WELL NUMBER \_\_\_\_\_

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line  
 SW SE SE

SEC. 28 TWP. 34 RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed \_\_\_\_\_

Plugging Commenced 2-24-88

Plugging Completed 3-15-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Edmiston Oil Co., Inc.

ADDRESS 1260 Ks. St. Bank Bldg.  
 Wichita, Kansas 67202

PHONE # (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	366'	none
				4-1/2"	4799'	3398'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4690' and 4 sacks cement. Shot pipe @ 3803', 3596', 3398', pulled a total of 88 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 18th day of March 19 88

Irene Hoover  
 Notary Public 1988

My Commission Expires:



RECEIVED  
 STATE CORPORATION COMMISSION  
 3-21-88  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 Form CP-4  
 Revised 07-86