


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 27 Twp. 34 Rge. (E) 12 (W)  
Location as "NE/CNW/SE/SW" or footage from lines C S/2 SE/4  
Lease Owner Oleum, Incorporated  
Lease Name Good Well No. 1  
Office Address Drawer 2232 - Longview, Texas 75601  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed May 8, 1977  
Application for plugging filed May 8, 1977  
Application for plugging approved May 8, 1977  
Plugging commenced May 8, 1977  
Plugging completed May 8, 1977  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bud Metz - Stafford, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4810 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface					
	Casing	0	306	8 5/8"	306	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug at 300' with 35 sacks cement,  
plug at 40' with 12 sacks cement,  
5 sacks in rate hole. Job completed  
at 1:00 P.M. May 8, 1977 by  
Allied Cementing Co.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 11 1977  
5-11-77  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Search Drilling Company (If additional description is necessary, use BACK of this sheet)  
Address Wichita, Kansas 67218

STATE OF Kansas COUNTY OF Sedgwick  
R. M. Stagl (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. M. Stagl  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of May, 19 77

My commission expires February 22, 1981  
Maxine Dressen Notary Public.



DRILLERS LOG

#1 GOOD

CASING RECORD:  
8 5/8" set at 306'  
with 225 sacks cement

OPERATOR: Oleum, Incorporated

DESCRIPTION:

CONTRACTOR: Search Drilling Company

C S/2 SE/4,  
Section 27-34S-12W  
Barber County,  
Kansas

TOTAL DEPTH:

COMMENCED: May 1, 1977

4810'

COMPLETED: May 8, 1977

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay Shale	0	175	
Shale	175	320	
Shale and Red Bed	320	507	
Shale	507	631	
Shale Anhydrite	631	1348	
Shale and Lime	1348	2370	
Lime and Shale	2370	3055	
Lime and Shale	3055	3608	
Shale and Lime	3608	4426	
Shale and Lime	4426	4750	
Lime	4750	4800	
Lime	4800	4810	
Rotary Total Depth	4810		

Dry and Abandoned

RECEIVED  
STATE CORPORATION COMMISSION

MAY 11 1977  
5-11-77  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

R. M. Stagl  
R. M. Stagl

Subscribed and sworn to before me this 9th day of May, 1977.

My appointment expires:  
February 22, 1981

Maxine Dressen  
Maxine Dressen Notary Public

