

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER. 15-007-212.92-0000

LEASE NAME Burgess

WELL NUMBER A-1

 Ft. from S Section Line

 Ft. from E Section Line
 SW SE SW

SEC. 27 TWP. 34 RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 3-29-88

Plugging Completed 4-12-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Edmiston Oil Company, Inc.

ADDRESS 1260 Ks. St. Bank Bldg.
Wichita, Kansas 67202

PHONE# (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	321'	none
				4-1/2"	4849'	3431'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4690' and 4 sacks cement. Shot pipe @3618', 3431', pulled a total of 84 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 8-5/8" plug and 100 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED, AND SWORN TO before me this 13th day of April, 19 88

RECEIVED
 STATE CORPORATION COMMISSION

Irene Hoover
 Notary Public

My Commission Expires:

APR 15 1988
4-15-88
 CONSERVATION DIVISION
 Wichita, Kansas




15-007-21292-0000
CONTRACTOR'S WELL LOG

OPERATOR: Ram Petroleum Corporation
CONTRACTOR: Union Drilling Co., Inc.
LEASE NAME: Burgess #1
LOCATION: SW SW SE Section 27-34S-12W
Barber County, Kansas
COMMENCED: November 16, 1981
COMPLETED: November 25, 1981

0	335	Redbed	Set 8-5/8" @ 321' w/300 sxs
335	678	Redbed & shale	common cement 2% gel, 3% CC
678	4022	Shale	
4022	4547	Shale & lime	
4547	4810	Lime	
4810	4850	Lime & chert	
4850		TD	

We certify that the above foregoing is a true and correct copy of the log on the Burgess #1, SW SW SE Section 27-34S-12W, Barber County, Kansas.

Union Drilling Co., Inc.



R. D. Messinger

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 1st day of November, 1981.

My appointment expires:

12-24-84


Shirely A. Gallegos
Notary Public



RECEIVED
STATE OF KANSAS CONSERVATION DIVISION

DEC 22 1987
12-22-87
CONSERVATION DIVISION
Wichita, Kansas