

API NUMBER 15-007-21,397-0000

LEASE NAME Burgess "B"

WELL NUMBER #3

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

330 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Gore Oil Company

ADDRESS 125 N. Market, Suite 1750, Wichita, KS 67202

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-3-90 (date)

by Dodge City (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4746' Bottom 4770' T.D. 4830'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	318	8 5/8"	318	0
		0	4839	4 1/2"	4839	3800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plug back with sand to 4700'. Dump 4 sx cement. Plug with 300# hulls, 10 sx gel, 50 sx 60/40 - 6%, 100# hulls, 10 sx gel, 100 sx 60/40 - 6% to surface. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheuerman (Employee of Operator) ~~xxxxxx~~
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Scott W Scheuerman

(Address) 125 N. Market, #1750, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 90

CONSERVATION DIVISION
 Wichita, Kansas

Rebecca K Crawford
 Notary Public



res: 1-7-91

CONTRACTOR'S WELL LOG

APR 2 1982

OPERATOR:
CONTRACTOR:
LEASE NAME:
LOCATION:

Ram Petroleum Corporation
Union Drilling CO., Inc.
Burgess "B" #3
SW SW SW Section 26-34S-12W
Barber County, Kansas
February 18, 1982
February 28, 1982

COMMENCED:
COMPLETED:

0	322	Redbed
322	1216	Redbed & shale
1216	4374	Shale
4374	4507	Shale & Lime
4507	4840	Lime
4840		TD

Set 8-5/8" @ 318' w/300
sacks common cement 2% gel,
3% Ca. Cl.

APR 2 1982

We Certify that the above foregoing is a true and correct copy of the log on the Burgess "B" #3, SW SW SW Section 26-34-12W, Barber County, Kansas.

Union Drilling CO., Inc.

R. D. Messinger
R. D. Messinger

STATE OF KANSAS)
)SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 09th day of March, 1982.

My appointment expires:
12-24-84

Shirley A. Gallegos
Shirley A. Gallegos
Notary Public



RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1990
2-14-90
CONSTRUCTION DIVISION
Wichita, Kansas