

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-22,294-00-00

LEASE NAME Davis Trust "B"

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

3300 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 11 TWP. 34 RGE. 15 (E) or (W)

LEASE OPERATOR TXO Production Corporation

ADDRESS 1660 Lincoln St. - Suite 1800 Denver, CO 80246

COUNTY Barber

PHONE# (303) 861-4246 OPERATORS LICENSE NO. 5171

Date Well Completed 3-26-90

Character of Well D&A

Plugging Commenced 3-26-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-26-90

The plugging proposal was approved on 3-21-90 (date)

by Dick Capp (KCC District Agent's Name).
to be filed

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5130

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 930' w/40 sacks cement thru drill pipe

Next Plug: @ 450' w/30 " " " " " 15 sacks in Rat Hole

Top Plug: @ 40' w/10 " " " " " 10 sacks in Mouse Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TXO Production Corporation


STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters therein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530

APR 09 1990
4-09-90
I, Dorothy M. Hogue, Notary Public, State of Kansas, do hereby certify that the above and sworn to before me this 4 day of April, 1990



My Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: March 16, 1990
DATE COMPLETED: March 26, 1990

TXO Production Corporation
DAVIS TRUST #1
C S/2 NE
Sec. 11, T34S, R15W
Barber County, Ks.

ELEVATION: 1620 K.B.

0 - 1425' Surface Soil, Shale
1425 - 3038' Lime & Shale
3038 - 3608' Shale & Lime
3608 - 4820' Lime & Shale
4820 - 4885' Chert & Lime
4885 - 5130' Lime
5130' RTD

Surface Pipe: Set new
8-5/8", 24# pipe @903'
w/250 sacks Lite 3% cc. &
150 sacks Class A 2% gel
3% cc.

A F F I D A V I T

STATE OF KANSAS,
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 4 day of March 1990.

Dorothy M Hague

