

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 South Market Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

DEC 16 1998

API NUMBER 15007-21068-00-00

DEC 11 1998

LEASE NAME Z-Bar Cattle Co.

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 60 days.

WELL NUMBER D-1

1990 Ft. from N/S Section Line

2310 Ft. from E/W Section Line

SEC. 33 TWP. 34 RGE. 15 XX or (W)

COUNTY Barber

LEASE OPERATOR Woolsey Petroleum

ADDRESS 1966 SE Rodeo Dr. P.O. Box 168 Medicine Lodge

PHONE# 316 886-5606 OPERATORS LICENSE NO. 5506

Date Well Completed N/A

Character of Well Good

Plugging Commenced 12-4-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-9-98

The plugging proposal was approved on 12-4-98 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Miss Depth to Top 4678 Bottom 4684 T.D. 4946 CIBP 4850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				16	60	None
				8 5/8	415	None
				4 1/2	4945	3250

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Lay down rods and tubing, set CIBP at 4650, dump 2sx cement, stretch and cut pipe at 3250  
lay down casing. Allied pump 300 hulls 10 jel, 50sx cement, 10 jel; 100 hulls 8 5/8 wiper  
100sx cement 60/40 6% jel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105


Address 107 W1 Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woolsey Petroleum

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) of above described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Alan Vratil

(Address) Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 10 day of December, 19 98

Glenda Morrison  
Notary Public

My Commission Expires: 11/30/04