

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barber County, Sec. 17 Twp. 34 Rge. 15W ~~2E~~ (W)

Location as "NE/CNW*SW*" or footage from lines NE NE SW
Lease Owner Barbara Oil Company
Lease Name Irma Brack Well No. 1
Office Address 322 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed March 23, 1954 19
Application for plugging filed March 23, 1954 19
Application for plugging approved March 23, 1954 (Verbally) 19
Plugging commenced March 23, 1954 19
Plugging completed March 23, 1954 19
Reason for abandonment of well or producing formation D&A

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5549 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				6"	56'	None
				10-3/4"	789'	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 5549 TD to 300' of top filled with heavy mud. Wood bridge set at 300'. 30 sacks cement by Halliburton. Filled cellar with heavy mud. 20 sacks cement in top of hole to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R.C. Patton Company
Address Orpheum Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L.W. Davidson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L.W. Davidson

322 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of March, 19 54

Mildred Gush
Notary Public.

My commission expires March 2, 1957

RECEIVED
STATE CORPORATION COMMISSION

MAR 27 1954 3-27-54

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 17 T 34 R 15W
BOOK PAGE 22 LINE 34

Barbara Oil Company,
 Irma Brack Well #1
 Comm. 2/13/54
 Comp. 3/23/54
 Total Depth 5549'
 Contractor R. C. Patton Co.,

Location, Ctr NE/4, NE/4, SW/4
 Section 17-T34S-15W Barber Co., Kansas.
 CASING RECORD.
 15 1/2 Casing at 56 Feet.
 Cemented with 100 Sacks Cement
 10 3/4" Casing at 789 Feet
 Cemented with 500 Sacks Cement

Sand	23
Red Clay	35
Red Rock	75
Sand	95
Red Bed & Shale	775
Shale & Shells	1100
Salt, Shale & Shells	1220
Gray Shale & Shells	1248
Shale & Shells	1880
Lime & Shale	1925
Anhydrite & Shale	2005
Lime	2105
Lime & Shale	2280
Shale	2365
Lime & Shale	3970
Shale Sandy	4015
Lime & Shale	4132
Lime Broken	4162
Lime, Shale & Chert	4220
Lime & Shale	4243
Lime Broken	4300
Lime & Shale	4414
Lime	4433
Lime & Shale	4551
Lime	4574
Shale	4596
Lime	4669
Lime & Shale	4725
Lime	4760
Lime & Shale	4840
Lime	4866
Shale	4891
Lime & Shale	4992
Shale	5077
Lime & Shale	5115
Lime	5155
Lime Cherty	5168
Lime	5315
Lime & Shale	5386
Sand	5402
Lime & Shale	5420
Lime	5458
Lime Chert	5491
Lime	5549
Total Depth	5549

STATE OF Kansas COUNTY OF Sedgewick ss,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

PLUGGING
 FILE SEC 17 T 34 R 15W
 BOOK PAGE 22 LINE 34

R. C. PATTON CO.,
 By R. C. Patton

Subscribed and sworn to before me this 26th day of March 1954

RECEIVED
 STATE CORPORATIONS COMMISSION

MAR 27 1954

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Kendrick
 Notary Public.

My Commission Expires Oct 4th 1956.