

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-007-00453-DD-DD

API NUMBER 9/02/44

LEASE NAME Davis

WELL NUMBER #3

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 14 TWP. 34 SRGE. 15 ~~15~~ (W)

COUNTY Barber

Date Well Completed 9/02/44

Plugging Commenced 12/07/91

Plugging Completed 12/26/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Knighton Oil Company, Inc.

ADDRESS 221 South Broadway-#710, Wichita, Ks. 67202

PHONE# (316) 264-7918 OPERATORS LICENSE NO. 5010

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/07/91 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Mississippian Depth to Top 4808 Bottom 4857 T.D. 5540

Show depth and thickness of all water, oil and gas formations.

RECEIVED

OIL, GAS OR WATER RECORDS

CASING RECORD (KANSAS CORPORATION COMMISSION)

Formation	Content	From	To	Size	Put In	Pulled out
Mississippian	Gas	4808	4857	10"	979	None
				7"	4808	3240'

JAN 17 1992

CONSERVATION DIVISION
WICHITA KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sand from 4857 to 4760. Seven sacks Class A w/dump bailer. 400 lbs. Hulls w/Gel. 70 sacks 60/40 Pozmix/6% Gel from 4760'. Mixed 1500 lb. gel and 200 lb. hulls and pumped into hole. Mixed and pumped 150 sacks 60/40 filled hole. Shut in @ 400 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P. O. Box 187, Medicine Lodge, Kansas 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Earl M. Knighton, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Earl M. Knighton, Jr.

(Address) 221 South Broadway-#710
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 16th day of January, 19 92

Sarah A. Simon
Notary Public

My Commission Expires: 12/11/93 Sarah A. Simon




Company - PHILLIPS PETRO.CO.
 Farm - Barber No. 1.

SEC. 14
 CSE NE

T. 34 R. 15 W

Total Depth. 5543'
 Comm. 4-29-44 Comp. 6-1-44
 Shot or Treated.
 Contractor.
 Issued. 12-23-44

County. Barber
 KANSAS



CASING:
 13 3/4" 990'

Elevation. _____

Production. 987,000 G.

Figures Indicate Bottom of Formations.

surface clay	10
red bed & shale	300
red bed & shale gyp	880
red bed & shale	1057
shale & shells	1200
shale	1490
shale & shells	1790
shale & lime shells	1542
shale, lime & sand	2022
shale & lime	2724
shale, sand & lime	2836
lime & shale	3662
shale & lime strks	3758
shale	3822
shale & lime	4038
shale & sand	4092
shale	4155
lime KC	4434
lime, sand & shale	4473
lime & chert	4498
lime	4523
lime & shale	4566
lime	4600
lime & shale	4769
lime & sand	4803
lime & chert sdy	4817
congl	4834
lime & shale	4857
lime	4897
lime & shale	5018
lime, shale & chert	5047
lime	5180
shale	5188
lime, shale chert	5219
lime	5247
lime & chert	5267
lime & shale	5279
lime & chert	5369
lime & shale	5396
lime, shale & sand	5427
lime	5449
shale & sdy lime	
strks	5500
lime & sand	5543
Total Depth	

K. G. S. LIBRARY