


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 11 Twp. 34S Rge. 15W (W)  
Location as "NE/CNW/SW" or footage from lines C NW NE  
Lease Owner Gensch & Holke  
Lease Name DAVIS RANCH Well No. 1  
Office Address 1527 Wichita Plaza Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 20 1965  
Application for plugging filed February 21 1965  
Application for plugging approved February 21 1965  
Plugging commenced February 21 1965  
Plugging completed February 21 1965  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archies Elving, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4815 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUMP IN	PULLED OUT
Red Bed & Sand	Surface Casing	-0-	885'	8-5/8"	885'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGED; Filled hole with mud from 4815' to 300';  
put in 1/2 sk. hells, plug & 25 sz.  
cement.  
Filled with mud from above 300' to 40';  
put in 1/2 sk. hells, plug & 10 sz.  
cement. Job completed at 10 a.m. 2-21-65.

RECEIVED  
STATE CORPORATION COMMISSION  
3-1-65  
MAR 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sierra Petroleum Co., Inc.  
Address 1015 Wichita Plaza Building, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF RUSSELL ss.  
G. A. Hall

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

G. A. Hall, Production Superintendent  
Box 232, Russell, Kansas 67665  
(Address)

Subscribed and Sworn to before me this 26th day of February, 1965

Shirley Dwyer  
Notary Public.

My commission expires 10-17-67

GENSCH & HOLKE - Operators

SIERRA PETROLEUM CO., INC. - Contractor

DAVIS RANCH #1  
C NW NE  
Sec. 11-34S-15W  
Barber County, Kansas

T. D.: 4815'  
Elev.: 1636 D.F.  
1639 K.B.

Commenced: 2-8-65  
Completed: 2-20-65

Casing:

8-5/8" Set at 885'

FORMATION

Redbed & Sand  
Shale & Shells  
Lime & Shale  
Lime

Cement:

with 300 sx. Pozmix w/ HA-5

DEPTH

885  
1915  
4148  
4815


RECEIVED  
STATE CORPORATION COMMISSION

MAR 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF RUSSELL ) ss:

I hereby certify that the above information is true and  
correct to the best of my knowledge.

  
G. A. Hall, Prod. Supt.

Subscribed and sworn to before me this 26th day of February,  
1965.

  
Notary Public

My commission expires: 10-17-67