

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31341
Name: Craig Oil Company
Address 1: 15 South Main
Address 2: _____
City: Russell State: Ks Zip: 67665 + _____
Contact Person: WARD Craig
Phone: (785) 483-1543
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3330 Bottom: 3341 T.D. 3341
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 167-19054-0001
Spot Description: _____
W2 NE SE Sec. 31 Twp. 13 S. R. 14 East West
1980 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Russell
Lease Name: Brown OWD Well #: 5
Date Well Completed: 11-25-1984
The plugging proposal was approved on: 6-20-2012 (Date)
by: CASE Morris (KCC District Agent's Name)
Plugging Commenced: 7-12-2012 7:45 A.M.
Plugging Completed: 7-12-2012 2:00 P.M.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		<u>SURFACE</u>	<u>8.625</u>	<u>904</u>	<u>0</u>
		<u>Production</u>	<u>4.50</u>	<u>3329</u>	<u>0</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RAN tubing to 725' Pumped 105 sx cement, w/200# Halls
Had cement to surface, but lost circulation.
POOH waited on cement, Rantubing in, Tagged cement, Pulled up to 325'
pumped 25 sx cement, w/150# Halls, cement circulated. POOH.
Topped off w/15 sx cement.

Plugging Contractor License #: 99977 Name: Quality Oil Well Cementing
Address 1: 740 W Wichita Ave. Address 2: _____
City: Russell State: KANSAS Zip: 67665 + _____
Phone: (785) 483-1071
Name of Party Responsible for Plugging Fees: WARD Craig
State of KANSAS County, Russell, ss. _____
WARD Craig (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Ward D. Craig KCC WICHITA