


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 22 Twp. 31S Rge. (E) 9 (W)
Location as "NE/CNW&SW" or footage from lines NW NW NW
Lease Owner E. H. Wood, Jr.
Lease Name Muir "B" Well No. 1
Office Address Insurance Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-25 1970
Application for plugging filed " 19
Application for plugging approved " 19
Plugging commenced " 19
Plugging completed " 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4483 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	248'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 245' 1/2 sk hulls and 25 sk cement
Mudded to 40' 1/2 sks hulls and 10 sks cement
2 sacks in rathole



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
505 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of December, 1970



[Signature]
Mary Ann Scott
Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: E. H. Wood, Jr. COMMENCED: 11-15-70
Insurance Building
Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. COMPLETED: 11-25-70
505 Union Center
Wichita, Kansas

SURFACE CASING: 8 5/8" new casing at LOCATION: Muir # 1 "B"
248' with 250 sacks NW NW NW
cement. Section 22-31S-9W
Harper County, Ks.

0	-	125	sod & sand
125	-	248	redbed & lime
248	-	1448	shale-shells
1448	-	1926	lime & shale
1926	-	2465	lime
2465	-	3660	lime & shale
3660	-	3721	sand-shale
3721	-	4254	lime
4254	-	4443	shale & lime
4443	-	4483	lime

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 - 1970
CONSERVATION DIVISION
Wichita, Kansas

The foregoing statement is correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John C. Graves*
John C. Graves, President

My Commission Expires July 28 , 1974

Mary Ann Scott
Mary Ann Scott, Notary Public

