


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Harper County, Sec. 16 Twp. 32S Rge. (E) 6W(W)

Location as "NE/CNW/SW" or footage from lines. C NW NE NE  
Lease Owner K & E DRILLING, INC.  
Lease Name M. E. Davis Well No. 1  
Office Address 719 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 3-17-66 19  
Application for plugging filed 3-17-66 19  
Application for plugging approved 3-17-66 19  
Plugging commenced 3-17-66 19  
Plugging completed 3-17-66 19  
Reason for abandonment of well or producing formation dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Eiving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4738 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	307'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud up to 275', solid bridge there and  
20 sx. cement. Heavy mud to 40' solid bridge  
& 10 sx. cement, 2 sx. in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 22 1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.

Address 719 Union Center, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Wayne L. Brinegar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne L. Brinegar  
Wayne L. Brinegar  
719 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of March, 1966

My commission expires 8-30-69 Julene M. Bannon Notary Public.



# DRILLER'S WELL LOG

OPERATOR: **K & E DRILLING, INC.**  
 719 Union Center  
 Wichita, Kansas 67202

WELL NAME: #1 M. E. Davis  
 LOCATION: C NW NE NE 16-32S-6W  
 Harper County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**  
 719 UNION CENTER BLDG.  
 WICHITA, KANSAS

COMMENCED: 3-2-66  
 COMPLETED: 3-17-66

CASING RECORD: 8-5/8" @ 307' w/175 sx.

ELEVATION: 1383' DF; 1386 KB

ROTARY TOTAL DEPTH: 4738

PRODUCTION: D & A

## FORMATION RECORD

*Depths shown indicate bottom of formations encountered.*

Shale & Red Beds	307
Shale & Shells	1485
Lime	3020
Shale & Lime	3220
Lime	4602
Shale	4688
Shale & Lime	4729
Lime	4738

**RECEIVED**  
 STATE CORPORATION COMMISSION

MAR 22 1966

CONSERVATION DIVISION  
 Wichita, Kansas

## CERTIFICATION

State of KANSAS  
 County of SEDGWICK

ss:

I, H. L. Wilson, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Subscribed and sworn to before me this 21st day of March, 19 66.

My Commission expires: 8-30-69

Julene M. Bannon  
 Notary Public.

