


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County, Sec. 16 Twp. 31 Rge. 9 (E) (W)  
Location as "NE/CNW/SW" or footage from lines. NE NE NW  
Lease Owner Santa Fe Pipe & Supply, Inc.,  
Lease Name Banning Well No. 1  
Office Address Box 562, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) gas  
Date well completed 10-21- 1959  
Application for plugging filed 11-5- 1966  
Application for plugging approved 11-7- 1966  
Plugging commenced 11-8- 1966  
Plugging completed 11-14- 1966  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4520' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	197'	none
				4-1/2"	4516.97'	3664.60'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4520'	-	4260'	-	plug
4260'	-	4224'	-	3 sacks cement
4224'	-	230'	-	mud
230'	-	210'	-	rock bridge
210'	-	135'	-	25 sacks cement
135'	-	40'	-	mud
40'	-	30'	-	rock bridge
30'	-	base	-	10 sacks cement

RECORDED  
DEC 12 1966  
12-12-66  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Santa Fe Pipe & Supply, Inc.,  
Address Box 562, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
T. L. Nutt (agent or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt  
Box 562, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of December, 1966

My commission expires July 31, 1970

Mary M. Guessier  
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas.

Rotary Drilling Commenced 10/8/59

Rotary Drilling Completed 10/21/59

LOCATION: #1 Banning  
NE NE NW Sec. 16-31-9W  
Harper County, Kansas.

CONTRACTOR: **FICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD:

197' of 8 5/8" surface casing cemented with 100 sacks cement, 2% gel, cement circulated.

Ran 146 jts. of 4 1/2" casing cemented with 100 sacks cement, 2% gel.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Circ. for samples:

15	Surface clay	4445'
132	Sand, gravel and clay	4460'
194	Red Bed	4470'
720	Red rock and shale	4495'
1100	Blue shale, gyp., and Anhydrite	4520'
1400	Salt shale and shells	
3763	Shale and lime	
4278	Lime	
4438	Lime and shale	
4520	Mississippi	
4520	Rotary Total Depth	

Slope Test:

2000'	0°
3000'	0°
4000'	0°

S.L.M.:

2000'	OK
3000'	OK
4000'	OK

RECEIVED  
STATE CORPORATION COMMISSION

DEC 12 1959

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Gerald W. Pike, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By Gerald W. Pike  
Attorney-in-Fact  
Partner

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 24 day of November, 19 59, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared Gerald W. Pike, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 13, 1961

Ruth M. Sullivan  
Notary Public  
Ruth Sullivan