


15-025-20004-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
11 No. Broadway  
Wichita, Kansas



Locate well correctly on above  
Section Plat

Clark County, Sec. 33 Twp. 32S Rge. 21W (X) (W)  
Location as "NE/CNW/SE" or footage from lines C NW SE  
Lease Owner North Star Petroleum Corporation  
Lease Name Truman C. York Well No. 1  
Office Address 1012 W. 10th Street, Amarillo, Texas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19\_\_\_\_  
Application for plugging filed 8-10-67 19\_\_\_\_  
Application for plugging approved 8-6-67 19\_\_\_\_  
Plugging commenced 8-6-67 19\_\_\_\_  
Plugging completed 8-6-67 19\_\_\_\_  
Reason for abandonment of well or producing formation Dry Hole.

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5422 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 725'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 700'  
Set plug and 35 sax cement  
Mud to 50'  
Set plug and 15 sax cement  
Mud to surface  
2 sax in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 11 1967

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bowers Drilling Company, Inc.  
Address 1434 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Emil E. Bowers (agent or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers  
1434 Wichita Plaza, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of August, 1967

Elaine D. Winter  
Notary Public.

My commission expires May 5, 1970.



WELL LOG

COMPANY: North Star Petroleum Corporation  
CONTRACTOR: Bowers Drilling Company, Inc.  
FARM: #1 Truman C. York  
LOCATION: C NW SE Section 33-32S-21W  
Clark County, Kansas  
COMMENCED: 7-24-67  
COMPLETED: 8-6-67  
ELEVATION: 1991 Ground

---

|             |                |                                   |
|-------------|----------------|-----------------------------------|
| 0 - 380     | Redbed         | 8-5/8" casing set @ 725 W/500 sax |
| 380 - 925   | Shale          |                                   |
| 925 - 1300  | Shale & Shells |                                   |
| 1300 - 2315 | Lime & Shale   |                                   |
| 2315 - 3046 | Lime           |                                   |
| 3046 - 4497 | Lime & Shale   |                                   |
| 4497 - 5305 | Lime           |                                   |
| 5305 - 5330 | Lime & Sand    |                                   |
| 5330 - 5422 | Lime           |                                   |
| 5422 -      | T.D.           | D & A                             |

---

LOG TOPS

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 11 1967  
CONSERVATION DIVISION  
Topeka, Kansas

---

STATE OF KANSAS        )  
                              ) SS  
COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Truman C. York located C NW SE of Section 33-32S-21W Clark County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas this 10th day of August, 1967.

Elaine L. Winter  
Notary Public

My commission expires May 5, 1970.