

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 5175-20944 0002

LEASE NAME McVey

WELL NUMBER 1-11

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

C - W $\frac{1}{2}$ -NE Ft. from S Section Line
Ft. from E Section Line

LEASE OPERATOR Midwestern Exploration Co.

SEC. 11 TWP. 33S RGE. 32W (W)

ADDRESS Box 1884 Liberal, Kansas 67901

COUNTY Seward

PHONE# (316) 624-3534 OPERATORS LICENSE NO. 5263

Date Well Completed 3-10-87

Character of Well Gas

Plugging Commenced 4-27-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-29-87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Steve Durant

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5641 Bottom 5753 T.D. 6240

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1585	none
				4 1/2	5895	4832

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pump 1 sk. of hulls & 20 sks. of cement to 5500

Pump 40 sks. of cement @ 1600

Pump 35 sks. of cement @ 700

Put 10 sks. of cement @ 40 to 0 Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward, ss.

Harold K. Frauli (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Harold K. Frauli

(Address) P.O. Box 1884 - Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 87



RECEIVED
STATE CORPORATION COMMISSION
Mary Morgan
Notary Public

My Commission Expires: August 3, 1988 MAY 12 1987

DRILLER'S LOG

McVey #1-11

CASING:	OPERATOR: Midwestern Exploration	DESCRIPTION:
8 5/8" at 1585' w/500 Sx LtWt, 2% CC + 200 sx Class C 2% CC	CONTRACTOR: Sage Drilling Co., Inc.	Sec. 11-33S-32W Seward County, KANSAS
TOTAL DEPTH: 6240'	COMMENCED: January 28, 1987	COMPLETED: February 9, 1987

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soils	0	150	
Clay & Sand	150	550	
Red Bed, Shale, Anhydrite	550	1585	
Lime & Shale	1585	1860	
Shale	1860	2345	
Lime & Shale	2345	6160	
Lime	6160	6240	
RTD	6240		

Logged hole,
Ran 4 1/2" casing set at
6240 w/150 sx Class H

I certify that this is a true and correct copy of the log on the above well to the best of my knowledge.

SAGE DRILLING CO., INC.


John R. Bartholomew

 John R. Bartholomew, President

Subscribed and sworn to before me this 12th day of February, 1987.

Peggy A. Clutter

My appt. expires:



RECEIVED
STATE CORPORATION COMMISSION

APR 22 1987

CONSERVATOR OF
Wichita, Kansas