

15-077-10166-00-00


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County, Sec. 28 Twp. 31S Rge. 9W (E) (W)

Location as "NE/CNW&SW&" or footage from lines NE SE NE
Lease Owner Mull Drilling Company
Lease Name Muir Well No. 1
Office Address 670 Fourth Nat'l Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed October 24, 1962 19____
Application for plugging approved October 25, 1962 19____
Plugging commenced October 31, 1962 19____
Plugging completed November 2, 1962 19____
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4499 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200	none
				XXXX		
				4 1/2	none	3871

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out cellar, worked pipe and measured T.D. Sanded to 4400' and dumped 3 sacks cement.

Worked pipe and shot @ 3919'-3850'. Pulled pipe.

Pulled pipe and plugged well with mud and built rock bridge @ 180'. Dumped 20 sacks cement and filled hole and rock bridge. Capped well with 10 sacks cement and cleaned and doped collar and threads.

RECEIVED
STATE CORPORATION COMMISSION

NOV 7 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. O. Forbes
Box 221 Great Bend, Kas.
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 1962

My commission expires July 23, 1966

Carolyn Herren Notary Public.



ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al
Wichita, Kansas

ROTARY DRILLING COMMENCED: 5-17-60

CONTRACTORS: Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 5-28-60

CASING RECORD: Set 8 5/8 @ 200' cmt.
w/135 sax cmt.
Set 4 1/2" csg. @ 4495 cmt.
w/125 sax cmt.

LOCATION: MUIR #1
NE SE NE 28-31S-9W
Harper County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

700'	Red Bed
2870'	Lime & Shale
3798'	Sandy Lime w/Shale
4103'	Lime w/Shale
4143'	Lime
4455'	Lime w/Shale
4495'	Mississippi Chert - Total depth

STATE CORPORATION COMMISSION

DEC 27 1962

CONSERVATION DIVISION
Wichita, Kansas


I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

R. James Gear
R. James Gear

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 15th day of June, 1960.



Madge N. Miller
Madge N. Miller, Notary Public