

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Harper County, Sec. 7 Twp. 32S Rge. (E) 5 (W)

Location as "NE/CNWxSWx" or footage from lines C NE SW  
Lease Owner Eugene J. Carter et al  
Lease Name Chevrax Well No. 1  
Office Address 335 Mesa, Eureka, Kansas 67045  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 6, 1970  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced November 6, 1970  
Plugging completed November 6, 1970  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein of Attica  
Producing formation Depth to top Bottom Total Depth of Well 4776 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	241'	8-5/8"	241'	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 230 Feet,  
1/2 sax Hulls, Plug and 25 sax Cement;  
Mud to 40 Feet, 1/2 sax Hulls and Plug  
bridged w/Kelly and 10 sax Cement to  
Base of Cellar; 2 sax Cement in Rat Hole.  
Job Completed @ 9:30 A.M. 11/6/70.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
T. M. McCaul, Jr. of Sage Drilg. Co. ~~employer of owner~~ ~~or manager or operator~~ of the above described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) *T. M. McCaul, Jr.*  
500 Bitting Bldg., Wichita, Kansas 67202  
(Address)

SWORN TO before me this 10th day of November, 1970



*Louise K. Whitted*  
Louise K. Whitted - Notary Public.

November 26, 1970.

DRILLERS LOG

CHEVRAUX NO. 1

CASING RECORD:	OPERATOR: Eugene J. Carter	DESCRIPTION:
8-5/8" @ 241' w/200 sax Cement	CONTRACTOR: Sage Drilling Co.	C NE SW Sec. 7-32S-5W Harper County, Kansas
TOTAL DEPTH: 4776'	COMMENCED: October 27, 1970	ELEVATION: 1343KB
	COMPLETED: November 6, 1970	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	245	
Shale & Red Bed	245	300	
Shale	300	947	
Anhydrite	947	995	
Shale, Shells & Lime	995	1072	
Lime & Shale	1072	2260	
Shale & Lime	2260	2530	
Lime & Shale	2530	3433	
Sand	3433	3498	
Shale	3498	3571	
Shale & Lime	3571	3675	
Lime	3675	4060	
Lime & Shale	4060	4335	
Lime	4335	4445	
Lime & Shale	4445	4680	
Lime	4680	4756	
Sand	4756	4776	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By J. M. M. Carl



Subscribed and sworn to before me this 10th day of November, 1970.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.