

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Harper

County, Sec. 33 Twp. 31S Rge. (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines SE/4 NW/4 SE/4

Lease Owner Pickrell Drilling Company

Lease Name Burgess Well No. 1

Office Address 705 Fourth National Bank Bldg.-Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 18, 19 61

Application for plugging filed April 18, 19 61

Application for plugging approved April 18, 19 61


Plugging commenced April 18, 19 61

Plugging completed April 18, 19 61

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel - Pretty Prairie, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4495 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	none -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 195'. Set Plug. Cemented with 15 sacks cement. Heavy mud to 35'. Set Plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

APR 26 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company

Address 705 Fourth National Bank Bldg. - Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. C. W. Sebitts

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg.-Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of April, 19 61

My commission expires September 24, 1962

Maxine Johnson  
Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company Rotary Drilling Commenced 4-6-61  
 705 Fourth National Bank Bldg.  
 Wichita 2, Kansas Rotary Drilling Completed 4-18-61

LOCATION: BURGESS #1 - SE/4 NW/4 SE/4  
 Section 33-31S-9W  
 Harper County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
 Wichita, Kansas

CASING RECORD: 200' (5 jts) 8 5/8" 20# Surface Casing with 140 sacks cement. Circulated  
 No Oil String run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for Samples</u>	
200'	Red Rock		
615'	Red Rock & Blue Shale	4430'	
1435'	Red Rock, shale & shells	4440'	
1730'	Shale & lime	4465'	
2275'	Lime	4470'	
3540'	Lime & shale	4485'	
3616'	Lime	4495'	
3730'	Lime & shale		
4188'	Lime	<u>Slope Test</u>	
4300'	Lime & shale	1435'	0°
4357'	Lime	2920'	0°
4424'	Lime & shale	3963'	0°
4495'	Mississippian T.D.	4300'	0°

S. L. M.

1915'  
 3245'  
 4085'  
 4424'

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 APR 26 1961  
 CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**  
 By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss.:

On this 25th day of April, 1961, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument, as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962  
Maxine Johnson  
 Maxine Johnson Notary Public