

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22183-00-00
Spot: NESWSE Sec/Twnshp/Rge: 9-33S-3E
674 feet from S Section Line, 1978 feet from E Section Line
Lease Name: MCCLUNG Well #: 1
County: COWLEY Total Vertical Depth: 3350 feet

Operator License No.: 33277
Op Name: COOPER, ALBERT L. DBA COOPER SER
Address: PO BOX 381
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3300		200 SX
SURF	8.625	200		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2013 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND @ 3000, 4 SXS, CIRC. CEMENT 350' -0'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/25/2013 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TBG @ 2780', COOPER SERVICE ESTABLISHED CIRCULATION & PUMPED 12 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT @ 2510'. CUT CASING @ 600'. LAYED DOWN 16 JOINTS 4 1/2" CASING (600'). 10-24-2013, RIH W/TBG @ 360', COOPER SERVICE ESTABLISHED CIRCULATION & PUMPED 140 SXS 60/40 POZMIX. SDON. TAGGED CEMENT PLUG @ 105'. 10-25-2013, RIH W/TBG @ 95', COOPER SERVICE ESTABLISHED CIRCULATION, & PUMPED 30 SXS 60/40 POZMIX TO SURFACE, CEMENT CIRCULATED. PLUG DOWN 3:00 PM 10-25-2013. DANIELS READY MIX CEMENT TICKET #029354, & 029365.

Remarks: COMPLIANCE / 10 YEAR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
01/16/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

DEC 26 2013

RECEIVED