

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24247-00-00
Spot: NESESW Sec/Twnshp/Rge: 9-33S-3E
1153 feet from S Section Line, 3152 feet from E Section Line
Lease Name: MCCLUNG Well #: 9-1
County: COWLEY Total Vertical Depth: 3255 feet

Operator License No.: 33277
Op Name: COOPER, ALBERT L. DBA COOPER SER
Address: PO BOX 381
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3260		190 SX
SURF	8.625	310		200 SX
T1	2.375	3160		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2013 5:00 PM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE CO. Phone: (316) 204-0072

Proposed
Plugging
Method:

AS PER KCC RULES & REGULATIONS/ SAND @ 3115, & 4 SXS, CIRC. CEMENT 360'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 10/07/2013 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9-26-13, DUMPED SAND, SANDED WELL BACK @ 3115', DUMP BAILED 4 SXS CEMENT ON TOP. TAGGED CEMENT @ 3060'. CUT CASING @ 2000', 1200'. LAYED DOWN 32 JOINTS 4 1/2" CASING (1200'). 10-4-13, RIH W/TBG @ 360', COOPER SERVICE ESTABLISHED CIRCULATION & PUMPED 105 SXS 60/40 POZMIX. SDON. TAGGED CEMENT PLUG @ 95'. 10-7-13, RIH W/TBG @ 90', COOPER SERVICE ESTABLISHED CIRCULATION, & PUMPED 30 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 3:00 PM 10-7-2013. DANIELS READY MIX CEMENT TICKET #029217, & 029224.

Perfs:

Top	Bot	Thru	Comments
3165	3175	CSG	

Remarks: COMPLIANCE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
07/16/14 (TECHNICIAN)

KCC WICHITA
DEC 26 2013
RECEIVED