

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22313-00-00
Spot: NWESW Sec/Twnshp/Rge: 28-31S-11W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: STEPHENSON Well #: 1
County: BARBER Total Vertical Depth: 4550 feet

Operator License No.: 3372
Op Name: DIXON ENERGY, INC.
Address: 8100 E 22ND N BLDG 300, STE 200
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3635		WITH 2 SX CMT
PROD	4.5	3982	2184	WITH 150 SX CMT
SURF	8.625	281		WITH 160 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/16/2013 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Revd. from: TJ DIXON Company: DIXON ENERGY Phone: (316) 264-9632

Proposed Plugging Method: SET CIBP @ 3635' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 12/16/2013 10:15 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 3635' & 2 SX CMT. SPOTTED PLUGS THROUGH TBG. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3685	3690		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

[Handwritten Signature]
01/16/14

(TECHNICIAN)

KCC WICHITA

DEC 19 2013

RECEIVED

RECEIVED

DEC 17 2013

KCC DODGE CITY

Form CP-2/3

[Handwritten Initials]