

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21365-00-00  
Spot: SWNE Sec/Twnshp/Rge: 10-12S-16W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: DICKINSON A Well #: 10  
County: ELLIS Total Vertical Depth: 3360 feet

Operator License No.: 5145  
Op Name: DREILING OIL INC  
Address: 1008 CODY AVE PO BOX 550  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3359		200 SX
SURF	8.625	128		75 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2013 11:00 AM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: IVAN R. EDSALL Company: DRILLING OIL INC. Phone: (785) 625-8327

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Topeka perforated 08/77 at 2762' - 2770'. Squeezed off w/43 sx cement.  
07/27/1991- Resqueezed w/35 sx cement.  
07/24/1991- Hole at 545' squeezed w/85 sx cement.  
11/13/2013- Casing leak at 2062' - 2556'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/19/2013 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Nabors perforated at 1600', 1020' and 125'. Western Well Service ran in hole with tubing to 3105'. Quality rigged to tubing and mixed and pumped 100 sx cement w/200 # hulls mixed in. Pulled tubing to 2515' and mixed and pumped 100 sx cement w/200 # hulls mixed in. Pulled tubing to 1045' and mixed and pumped 60 sx cement w/200 # hulls to circulate cement to surface. Pulled tubing. Rigged to 4 1/2" casing and pumped 30 sx cement to circulate cement up 8 5/8" casing at 200-300 psi. 8 5/7" casing was on a hanger. No shut in pressure.

GPS: 39.02791 -099.07896  
4226' FSL 991' FEL  
SW SW NE NE

Perfs:

Remarks: QUALITY OIL WELL CEMENTING TICKET # 7582

Plugged through: TBG

KCC WICHITA  
DEC 27 2013  
RECEIVED

District: 04

Signed [Signature] (TECHNICIAN) CM  
01/16/14

DEC 19 2013