

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20072-00-00  
Spot: NWNWNESE Sec/Twnshp/Rge: 15-13S-19W  
2334 feet from S Section Line, 1092 feet from E Section Line  
Lease Name: STRAILEY Well #: 1  
County: ELLIS Total Vertical Depth: 3745 feet

Operator License No.: 5145  
Op Name: DREILING OIL INC  
Address: 1008 CODY AVE PO BOX 550  
HAYS, KS 67601

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 3700       |             | 200 SX   |
| SURF   | 8.625 | 164        |             | 125 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2013 12:30 PM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: IVAN R. EDSALL Company: DRILLING OIL CO Phone: (785) 625-8327

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement and 500 # hulls.  
Holes in casing.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/18/2013 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Nabors Completion and Production Services perforated at 2150', 1325' and 150'. Western Well Service ran in hole with tubing to 3516'. Quality rigged to tubing and mixed and pumped 150 sx cement w/150 # hulls mixed in. Pulled tubing to 2150' and pumped 150 sx cement w/200 # hulls mixed in. Pulled tubing to 515' and pumped 85 sx cement w/150 # hulls mixed in to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing w/40 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 10 sx cement to circulate cement up 5 1/2" casing.

GPS: 38.92077 -099.41346


Perfs:

Remarks: QUALITY OILWELL CEMENTING CO. TICKET # 7626

Plugged through: TBG

KCC WICHITA  
DEC 27 2013  
RECEIVED

District: 04

Signed  (TECHNICIAN)  
01/16/14

CM

DEC 19 2013