

1041328

TO: STATE CORPORATION COMMISSION

12-10

API NUMBER 15-007-21,068-00-00  
E2 E2 NW SEC. 33, T 34 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 1990 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME Z-BAR VALLTE CO. WELL # D-1

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER 160.75

OPERATOR LICENSE # 5506

WELL TOTAL DEPTH 4946 FEET

OPERATOR: WOOLSEY PETROLEUM CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 4949' WITH 175 SX

NAME AND PO BOX 168 SURFACE CASING: SIZE 8 5/8" @ 400' WITH 400 SX

ADDRESS MEDICINE LODGE, KS 67104 CONDUCTOR CSG: SIZE 16" @ 60' WITH NA SX

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 10 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 4884-96, CIBP @ 4850', PERFS AT 4678-84'

CIBP AT 4650' AND 2 SX CEMENT. CUT AND LAY DOWN CASING. FROM SURFACE PUMP 300# HULLS-10 SX

GEL-50 SX CEMENT-10 SX GEL-100# HULLS-8 5/8" WIPER PLUG AND 100 SX CEMENT.

RECEIVED

KANSAS CORPORATION COMMISSION

DEC 16 1998

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE WICHITA, KS

OPERATIONS COMPLETED: HOUR: 9:30 AM DAY: 10 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 4650' AND PUT 2 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER.

2ND PLUG PUMP DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS- 10 SX GEL- 50 SX CEMENT- 10 SX GEL-

100# HULLS- 8 5/8" WIPER PLUG- & 100 SX CEMENT. MAXIMUM PSI PRESSURE AT 200#. SHUT IN AT

0#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3250' OF 4 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

DEC 17 1998 60465