

1 040016

11-19-87

API NUMBER 15-007-20,918-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2 SW, SEC. 31, T 34 S, R 15 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

660 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Ballet Ranch Well # 1

Operator: TXO Production Corporation
Name & Address 155 North Market, Suite 1000
Wichita, KS 67202

County Barber 165.75

Well Total Depth 5100 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 943

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:50 a.m. Day: 19 Month: 11 Year: 19 87

Plugging proposal received from Allen Dick

(company name) TXO Production Corporation (phone) 316-886-5606

were: 4 1/2" at 5096' PBD 4900' Perfs at 4754-64' (Hertha) Elevation 1692' GL

1st plug pump 2 sx hulls and 20 sx common cement to 4700',

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:35 a.m. Day: 19 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped through 4 1/2" casing with 200 lbs. hulls and 20
sx cement. Squeezed to 1500 psi. Used common cement,

2nd plug pumped down 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 100-900 psi and shut in 400 psi.

Remarks: Used common cement and 60/40 Pozmix 2% gel by B.J. Titan. Recovered 3500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
NOV 25 1987

(did ~~not~~) observe this plugging.

INVOICED

Signed Stephen J. Pfeiffer (TECHNICIAN)

DATE 12-3-87

INV. NO. 19076