

1050350

15-007-21048-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Not Available

C SE \_\_\_\_\_, SEC. 29, T 34 S, R 15 W/E  
1320 feet from ~~N~~ SE Corner of ~~N~~ section line  
1320 feet from ~~N~~ SE Corner of ~~N~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8778

Lease Name Brownback Well # 1-29

Operator: Midwestern Supply Co., Inc.

County Barber

Name & Address 300 Patton Road

Well Total Depth 4950 160.88 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 894

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 7:00 am Day: 27 Month: September Year: 19 84

Plugging proposal received from Mike Kelso

(company name) Kelso (phone) 316-938-2457

were: PBTD 4885 4 1/2" set at 4950' Tubing & Rods in the bottom

1st plug push plug to 4600' and sand back 50' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug, and pump 150 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:00 am Day: 27 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4950' PBTD 4885' Tubing & Rods in the bottom

1st plug pushed plug to 4600' and sanded back 50' and dumped 4 sx cement on top of sand through bailer, 2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1

sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

OCT 01 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If not observed) observe this plugging.

DATE 10-8-84

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 4115