

1 041206

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 007-22,514-00-00  
NE SW NE, SEC. 28, T 34 S, R 15 W/E  
1650 feet from NE section line  
1650 feet from E section line

9-13

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506  
Operator: Woolsey Petroleum Corporation  
Name & Address: 107 N. Market, Ste. 600  
Wichita, KS 67202-1807

Lease Name Ballet Ranch Well # 1  
County Barber  
Well Total Depth 724 <sup>35.00</sup> feet  
Conductor Pipe: Size 13 3/8 feet 56  
w/60 sx cement  
Surface Casing: Size none feet

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Co. Inc. License Number 5929  
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 6:45 p.m. Day: 27 Month: 8 Year: 19 96

Plugging proposal received from Joe  
(company name) Duke Drilling Co. Inc. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe  
Lost circulation at 675'. Pumped 450 sx cement through drill pipe at 220'.

RECEIVED  
KANSAS CORP COMM  
1996 SEP 17 10:55 AM

Plugging Proposal Received by Steve Pfeiffer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 9:30 p.m. Day: 13 Month: 9 Year: 1996

ACTUAL PLUGGING REPORT 8/27/96 Pumped 450 sx cement through drill pipe at 220'. Had good  
returns but cement did not circulate. Hole caved in and bridged off below drill pipe depth  
at 220' (plug depth).

9/13/96 Cement was up into pipe at 42'. Ran 1" to 40' and pumped 20 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton.  
(If additional description is necessary, use BACX of this form.)

**INVOICED** (to be observed) observe this plugging.

DATE SEP 23 1996

Signed Steve Pfeiffer  
(TECHNICIAN)

INV. NO. 465574  
9-13 JAN 06 1997