

To: 1 040690
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-21 API NUMBER 15- 007-22,277-00-00 141
C SW, SEC. 14, 'T. 34 S, R 15 W/4

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: Marathon Oil Company
Name: Marathon Oil Company
Address P.O. Box 689
Oklahoma City, OK 73101

1320 feet from S section line
3960 feet from E section line
Lease Name Davis Trust Well # A-1
County Barber 166.36
Well Total Depth 5119 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 863

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 21 Month: 8 Year: 1992
Plugging proposal received from Vernon Schrant
(company name) Marathon Oil Company (phone) 405-720-5555

were: 4 1/2" at 4983' w/125 sx cement, PBSD 4960', Perfs at 4805-55'
1st plug sand back to 4750' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:45 a.m. Day: 21 Month: 8 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 4750' and dumped 4 sx cement on top of sand
bridge through bailer.
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 900 psi and shut in 700 psi.

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1992

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4200' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE 8-27-92
INV. NO. 36065

Signed Stephen J. Purje
(TECHNICIAN)