

1 051280.

3-26

174
-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,294
C. 9/2 NE, SEC. 11, T. 34 S, R. 15 W E
3300 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5121

Lease Name Davis Trust Well # 1

Operator: TXO Production Corporation
Name &
Address 1660 Lincoln St
Suite 1800
Denver, Colorado 80246

County Barber 166.73
Well Total Depth 5130 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 903

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Lobo Drilling Company License Number 5864

Address 310 W Central #117 Wichita KS 67202

Company to plug at: Hour: 9:00 am Day: 26 Month: March Year: 1990

Plugging proposal received from Ervin Neighbors

(company name) Lobo Drilling Company (phone) 316-267-1331

were: To fill hole with heavy mud and spot cement through drill pipe

1st plug @ 930' with 40sx cement

2nd plug @ 450' with 30sx cement

3rd plug @ 40' with 10sx cement

4th plug circulate rat hole with 15sx cement 5th plug circulate

mousehole with 10sx cement Plugging Proposal Received by Glen Barlow

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:00 pm Day: 26 Month: March Year: 1990

ACTUAL PLUGGING REPORT 1st plug @ 930' with 40sx cement

2nd plug @ 450' with 30sx cement

3rd plug @ 40' with 10sx cement

4th plug circulate rat hole with 15sx cement

5th plug circulate mousehole with 10sx cement

Remarks: Used 60/40 pozmix 6% gel By B.J. Titan

If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

(state) did not observe this plugging.

DATE 4-9-90

APR 02 1990

Signed Richard W. Lacy
(TECHNICIAN)

NOV. NO. 27810

CONSERVATION DIVISION
Wichita, Kansas