

To: 1 040736  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2-9

API NUMBER 15- 007-22,253-00-00 21 R  
NE SW SW, SEC. 8, T 35 S, R 13 W/E  
1249 feet from S section line  
4219 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171  
Operator: Marathon Oil Corp.  
Name:  
Address RR 1, Box 25  
Medicine Lodge, KS 67104

Lease Name Sternberger Well # A-2  
County Barber 164.54  
Well Total Depth 5063 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 405

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10 a.m. Day: 9 Month: 2 Year: 19 93

Plugging proposal received from Jeff Sletto  
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5063' w/150 sx cement, PBD 5027', Perfs at 4834-94'  
1st plug set CIBP at 4800' and dump 2 sx cement on top of plug through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 100 sx cement.

KANSAS RECEIVED  
COMMISSION

Plugging Proposal Received by Steve Pfeifer

FEB 17 1993  
STEVE PFEIFER  
(TECHNICIAN)  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Operations attended by Agent?: All  Part   
Operations Completed: Hour: 10:45 a.m. Day: 9 Month: 2 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4800' and dumped 2 sx cement on top of plug  
through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Maximum pressure 400 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3750' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE 2-22-93  
INV. NO. 37409

Signed Stephen J. Pfeifer  
(TECHNICIAN)